



Pavers on Setting Bed.

Nonwoven Filter Fabric.

Extruded Polystyrene Insulation.

Tremdrain 1000 or 2000.

Paraseal or Deckseal. (HDPE Side Up, Temporary Tape at 1.5" (3.8cm) Lap Seams. Use Permanent Seam Tape if Flood Testing is Scheduled.)

Concrete Roof Deck.

1.5"
(3.8cm)

Roof Deck With Pavers and Drainage. (Also See RDP-08)

No.	Date	Description	By
TREMCO 3735 Green Road Beachwood, Ohio 44122 216-292-5000			
Project: Roof Decks / Planters			
Drawn by:	Scale:	Date:	Drawing Index No.
J. Davis	Not To Scale	07/09/01	RDP-04